

Resin Flooring Specialists

Information Download

Terrazzo Preformed Joints

In situations where Resin Terrazzo flooring is to be installed over existing construction joints, day joints in the substrate, or a substrate build up transition (i.e screed to timber), it will usually be necessary to 'mirror' a joint through to the finished floor.

By far the cleanest and aesthetically pleasing floor joint is via the use of a preformed jointing strip.

We use high quality preformed joints from a German manufacture to achieve a high quality joint, with the advantage that the joint can often be RAL colour matched to the finished floor colour.

Below is a photo of a preformed joint installed in a doorway, which mirrors through a joint which existed in the screed substrate.



The preformed joint can be ground down with the Terrazzo, eliminating any lipping along the length of the joint.

The preformed joints are available in a wide range of depths and widths to cover most common requirements.

